

Technical specifications

Data Center Arezzo (IT1)

RATING 4 CERTIFIED MAXIMUM RELIABILITY

General

Total surface area: 5.000 m²

Data hall net surface area: 1.500 m²

- ✓ Secure location in terms of earthquakes
- ✓ Secure location in terms of hydro-geological risks

Structure

Usable height of the data hall: 3 m

Certifications and compliance

- ✓ ANSI/TIA 942-B-2017 Rating 4 (formerly Tier 4)
- ✓ GO - Guarantee of Energy Origin
- ✓ Code of Conduct for Data Center Energy Efficiency
- ✓ ISO 9001 - Quality of services offered
- ✓ ISO 27001 - IT security
- ✓ ISO 50001 - Energy management system
- ✓ ISO/IEC 27017 – Cloud security controls
- ✓ ISO/IEC 27018 – Managing personal data on the Cloud
- ✓ ISO/IEC 27035 – Managing security incidents and events

Services

Colocation solutions: rack portions; dedicated racks

Power per rack: up to 40kW

- ✓ 24h Smart hands & eyes
- ✓ 24h Systems management

Connectivity

Point of entrance: 4

Entrance Room: 2

Main Distribution Area (MDA): 2

- ✓ Carrier neutral data center
- ✓ Provision of managed connectivity
- ✓ Ultra-redundant connection with (IT2) via multi-fiber cables, running along two different routes

Energy

Total power: 4MW (redundant)

UPS redundancy: 2 N+1

UPS type: double conversion static

Individual UPS power: 500kVA

UPS run time: 30 minutes (standard) - 15 minutes (minimum)

Generator redundancy: 2N

Generator type: diesel generator units

Full load run time: 48h without refueling

Cooling

Dual cooling system: chilled water + gas direct expansion with Dynamic Free Cooling

Cooling system redundancy: 2N

Security

- ✓ CCTV
- ✓ Separate parking for employees/visitors
- ✓ 24/7/365 security
- ✓ Network Operations Center (NOC) 24/7/365
- ✓ Building Management System (BMS)

Fire prevention

Air replacement: integrated in DFC system

Extinguishing system: inert gas Extinguishing gas: IG-100

- ✓ Highly sensitive smoke detection system
- ✓ Underfloor liquid loss detection system



Data Center Arezzo (IT1)

Via Gobetti, 96 - 52100 Arezzo

Main nearby airports

Florence (FLR): 1 h
Rome (FCO): 2h 15 min

Nearby railway stations

Arezzo: 10 min
Florence: 1 h

Nearby motorway tollbooths

Arezzo (A1): 10 min

Estimated average time by car.

